

Stages of Inspection- On-Site Sewage System

Test Pit: Prior to Applying for permit(Site Evaluation)
Base Cut Excavation: prior to placing septic sand
Sand Inspection: during placing of septic sand
Pipe & Stone: prior to backfill
Septic Tank(s): Prior to backfill
Electrical/ Drawdown Test: upon completion of electrical work
occupancy/use: after rough grading
Septic Final: after grass growth or site stabilized(erosion control)